

बिहार सरकार
भवन निर्माण विभाग।

प्रेषक,

ई0 सुरेश प्रसाद प्रभाकर,
अभियंता प्रमुख-सह-अपर आयुक्त-सह-विशेष सचिव।

सेवा में,

मुख्य अभियंता (पटना),
भवन निर्माण विभाग,
बिहार, पटना।

विषय:-

प्रस्तावित वरीय आवासन, छज्जूबाग में वरीय पुलिस पदाधिकारीयों एवं वरीय सिविल पदाधिकारीयों, डी-टाईप, एनेक्स भवन तथा गार्ड रूम भवन का निर्माण हेतु तकनीकी अनुमोदित प्राक्कलन पर प्रशासनिक स्वीकृति प्रदान किये जाने के संबंध में।

प्रसंग:-

मुख्य वास्तुविद्, भवन निर्माण विभाग, पटना का पत्रांक:- 22 वास्तु0 (अनु0) दिनांक:- 13.01.2025

महाशय,

उपर्युक्त विषयक प्रासंगिक पत्र के आलोक में मुख्य वास्तुविद्, भवन निर्माण विभाग, पटना द्वारा प्राप्त अनुमोदित स्थल प्लान, वास्तुविदीय नक्शों एवं कुर्सी क्षेत्रफल दर आधारित CPWD - PAR-2023 के आधार पर स्थूल प्राक्कलन का गठन किया गया, जो निम्नवत है:-

SL. No.	Name of Work	Estimated Cost (In Rs.)
1.	ESTIMATE FOR CONSTRUCTION OF PROPOSED SR. POLICE OFFICER'S & SR. CIVIL OFFICER'S , D- TYPE , ANNEXE & GUARD ROOM BUILDING AT CHAJJUBAGH, PATNA, BIHAR.	₹ 7124.62 Lakh

उक्त गठित प्राक्कलन पर सक्षम प्राधिकार द्वारा तकनीकी अनुमोदन प्रदान कर दिया गया है। तकनीकी अनुमोदित प्राक्कलन (मूल में) संलग्न करते हुए प्रशासनिक स्वीकृति कि अग्रेत्तर कार्रवाई हेतु उपलब्ध करायी जा रही है।

अनु0:- यथोक्त।

विश्वासभाजन,

ह0/-

(ई0 सुरेश प्रसाद प्रभाकर)

अभियंता प्रमुख-सह-अपर आयुक्त-सह-विशेष सचिव।

ज्ञापांक:-.....

पटना, दिनांक:-.....2025

प्रतिलिपि:- निदेशक अनुश्रवण, भवन निर्माण विभाग, बिहार, पटना को सूचनार्थ प्रेषित। (प्राक्कलन की प्रति वेबसाइट <https://state.bihar.gov.in/bcd/CitizenHome.html> पर उपलब्ध है)

ह0/-

(ई0 सुरेश प्रसाद प्रभाकर)

अभियंता प्रमुख-सह-अपर आयुक्त-सह-विशेष सचिव।

ज्ञापांक:-.....

पटना, दिनांक:-.....2025

प्रतिलिपि:- मुख्य वास्तुविद्, भवन निर्माण विभाग, बिहार, पटना को प्राक्कलन की एक प्रति के साथ सूचनार्थ एवं अग्रेत्तर कार्रवाई हेतु प्रेषित।

अनु0:- यथोक्त।

ह0/-

(ई0 सुरेश प्रसाद प्रभाकर)

अभियंता प्रमुख-सह-अपर आयुक्त-सह-विशेष सचिव।

ज्ञापांक:-.....

पटना, दिनांक-.....2025

प्रतिलिपि:- विद्युत मुख्य अभियंता, भवन निर्माण विभाग, बिहार, पटना को प्राक्कलन की प्रति के साथ सूचनार्थ एवं आवश्यक कार्रवाई हेतु प्रेषित।

अनु०:- यथोक्त।

ह०/-

(ई० सुरेश प्रसाद प्रभाकर)

अभियंता प्रमुख-सह-अपर आयुक्त-सह-विशेष सचिव।

पटना, दिनांक-.....2025

ज्ञापांक:-.....

प्रतिलिपि:- कार्यपालक अभियंता, अग्रिम योजना प्रमंडल संख्या:-2, भवन निर्माण विभाग, पटना को प्राक्कलन की प्रति के साथ सूचनार्थ प्रेषित।

अनु०:- यथोक्त।

ह०/-

(ई० सुरेश प्रसाद प्रभाकर)

अभियंता प्रमुख-सह-अपर आयुक्त-सह-विशेष सचिव।

पटना, दिनांक-.....2025

ज्ञापांक:-.....1120(1)

प्रतिलिपि:- आई०टी० मैनेजर, भवन निर्माण विभाग, बिहार, पटना को विभागीय वेबसाइट पर अपलोड करने हेतु निदेश दिया जाता है कि प्राक्कलन की प्रति को अपलोड करना सुनिश्चित करें।

अनु०:- प्राक्कलन की प्रति।

(ई० सुरेश प्रसाद प्रभाकर)

अभियंता प्रमुख-सह-अपर आयुक्त-सह-विशेष सचिव।

ESTIMATE FOR CONSTRUCTION OF PROPOSED SR. POLICE OFFICER'S & SR. CIVIL OFFICER'S, D- TYPE, ANNEXE & GUARD ROOM BUILDING AT CHAJJUBAGH, PATNA, BIHAR.

ESTIMATE BASED ON CPWD PLINTH AREA RATE 2023

GENERAL ABSTRACT OF COST

SI.No.	Name Of Work	Cost In Rs.
1	A. SR. POLICE OFFICER'S & SR. CIVIL OFFICER'S BUILDING (B+G+7)	46,48,73,170
	B. D-TYPE BUILDING (G+7)	17,14,14,134
	C. ANNEXE BUILDING (G+3)	4,72,43,895
	C. GUARD ROOM(G)-2 Nos.	14,00,621
	E. Internal Road & Boundary Wall	1,00,82,100
	F. SPECIALISED E&M WORKS	1,06,68,000
2	CONTINGENCY @ 1.0 % upto Rs.100 Lac @ 0.5 % Above Rs.100 Lac	(I) 70,56,81,921 1,00,000 34,78,410
3	M.R. Provision for Split AC (For Annexe Building) 8.00 Nos. @ Rs 65000 / Nos.	(II) 35,78,410 5,20,000
4	Furniture/Furnishing (For Annexe Building) @ 10% of Building cost (a) of:- ANNEXE BUILDING (G+3) 2,68,14,343 10%	(III) 5,20,000 26,81,434
	GRAND TOTAL(I+II+III+IV)	71,24,61,765
	Say Rs. 7,124.62 Lakh	

NOTES :-

- 1 Estimate is based on Site Plan Approved by File No.- 438-9/2024 & Signed by Chief Architect, BCD, Patna Dtd.:- 03.01.2025
- 2 Rates are based on the CPWD Plinth Area Rates 2023
- 3 10% Extra shall be added, if approval is granted after 6 months.
- 4 After 12 months estimate shall be revised.
- 5 Sl. No. 4 is Approved by Competent Authority.

[Signature]
23.01.25
J.E.
Adv. Planning Div.-2
BCD, Patna

[Signature]
24/01/25
A.E.
Adv. Planning Div.-2
BCD, Patna

[Signature]
24-01-25
E.E.
Adv. Planning Div.-2
BCD, Patna

[Signature]
24/01/25
E.O.
Adv. Planning Circle
BCD, Patna

[Signature]
24/01/25
I.A.
Adv. Planning Circle
BCD, Patna

[Signature]
27.1.25
S.E.
Adv. Planning Circle
BCD, Patna

Technically approved for am. Rs 7124.62 lakhs (seven thousand one hundred twenty four lacs and sixty-two thousand rupees) only.

[Signature]
27.1.25
Chief Engineer (Design)
Building Construction Department
Bihar, Patna

ESTIMATE FOR CONSTRUCTION OF PROPOSED SR. POLICE OFFICER'S & SR. CIVIL OFFICER'S, D- TYPE, ANNEXE & GUARD ROOM BUILDING AT CHAJJUBAGH, PATNA, BIHAR.

ESTIMATE BASED ON CPWD PLINTH AREA RATE 2023

A.

SR. POLICE OFFICER'S & SR. CIVIL OFFICER'S BUILDING (B+G+7)

AREA STATEMENT

Ground Floor	15333.00 sft	or	1425.00 sqm
1st Floor	14418.40 sft	or	1340.00 sqm
2nd Floor	14418.40 sft	or	1340.00 sqm
3rd Floor	14418.40 sft	or	1340.00 sqm
4th Floor	14418.40 sft	or	1340.00 sqm
5th Floor	14418.40 sft	or	1340.00 sqm
6th Floor	14418.40 sft	or	1340.00 sqm
7th Floor	14418.40 sft	or	1340.00 sqm
Built up area	116261.80 sft	or	10805.00 sqm
Basement Floor	15333.00 sft	or	1425.00 sqm
Total Built up Area	131594.80 sft	or	12230.00 sqm

Sl. No.

DESCRIPTION

QUANTITY UNIT

RATE

AMOUNT

BUILDING COST (Specification as per Anx-I)

1	1.1	RCC Framed Structure (upto Six Storeys)	10,805.00	Sqm	@ RS	23530	/sqm	254241650
	1.1.2	Floor height 3.00 mt	1340.00	Sqm	@ RS	120.00	/Sqm	160800
	1.3.1	Set of Six additional storey (i.e from 7th to 12th storey)	10805.00	Sqm	@ RS	421.00	/Sqm	4548905
	1.3.2	Every 0.3 mtr. Or part thereof, additional height of floor above normal floor height of 3.60 mtr (on areas having less height). (3.30-3.00)/0.30)*421=421.00	10805.00	Sqm	@ RS	421.00	/Sqm	4548905
	1.3.3	Every 0.30 m or part thereof, higher plinth height over normal plinth height of 0.60 metre (on ground floor area only) Proposed plinth height =1.2 mtr =((1.2-0.6)/0.3)*421=842.00	1425.00	Sqm	@ RS	842	/Sqm	1199850
	1.3.7	Pile foundation upto a depth of 15 metro (on ground floor area only)	1425.00	Sqm	@ RS	10460	/Sqm	27730500
	1.4	Basement floor	1425.00	Sqm	@ RS	890	/Sqm	10884700
	1.4.1	Floor height upto 3.35 metre including water proofing (excluding raft base)	1,425.00	Sqm	@ Rs	23610	#REF!	33644250
	1.5	Fire Fighting	12230.00	Sqm	@ RS	600	/Sqm	7338000
	1.5.2	With wet riser system	12230.00	Sqm	@ RS	600	/Sqm	7338000
	1.6	Fire Alarm System	12230.00	Sqm	@ RS	600	/Sqm	7338000
	1.6.2	Automatic Fire alarm system	12230.00	Sqm	@ RS	600	/Sqm	7338000
	1.3.5	Making stronger foundations to take load of one additional floor (on ground floor area only)	1425.00	Sqm	@ RS	1820	/Sqm	2593500
2	2.1	Internal water supply and sanitary Installations @ 9 % of building basic cost(a)	9%					54460450
	2.2	External service connection						23305622
	2.2.1	Electrical External Service Connection @ 3.75 % of building basic cost(a)	3.75%					9710676
	2.2.2	Civil External Service Connection @ 1.25 % of building basic cost	1.25%					3236892
	2.3	Internal electric installations @12.5% of building basic cost(a)	12.5%					32368919
	2.4.1	Power wiring and Plugs						

Total Rs. 258951355 ..(a)

Total Rs. 287881705 ..(A)

Total Rs. 54460450 ..(B)

@ 4.0% of building basic cost(a)

4.0%

- 3 3.0 LIFTS with power operated centre opening doors and AC variable voltage & variable frequency controls.
3.1 Passenger Lift.
3.1.2 Passenger Lift. (13 prsn)

Total Rs. 10358054
Total (A+B+C) Rs. 78980163
(BUILDING+Services) PAR 421322318
3,202 /Sft

- 4 4.0 RCC WATER TANK
4.1 Overhead tank without independent staging
4.5 Underground sump

4 No. @ Rs 2399100 each
Total Rs. 9596400 ..(E)

30000 ltr. @ Rs 23 /ltr. 690000

100000 ltr. @ Rs 23 /ltr. 2300000
Total Rs. 2990000 ..(F)

5 5 DEVELOPMENT OF SITE

- 5.1 Levelling
5.3 External Sewerage
5.4 Filtered water Supply
5.4.1 Distribution lines up to 100mm dia
5.4.2 Peripheral grid 150mm to 300 mm dia pipes
5.4.3 Unfiltered water supply distribution lines.
5.5 Storm water drain.
5.6 Rain water Harvesting (RWH)
5.7 Trenches for services.
5.9 Horticulture work

@ 7.5% of basic building cost (a)
258951355.00

7.50%

- 6 6.8 Solar Photo Voltaic Power Generation System

Total Rs. 19421352
19421352 ..(G)

- 6.10.2 CCTV System

50.00 kWp @ RS 58480 /kWp 2924000

- 6.16.1 Lan System

12230.00 Sqm @ RS 210 /Sqm 2568300

10805.00 Sqm @ RS 560 /Sqm 6050800

Total Rs. 11543100
Total (D+E+F+G+H) Rs. 464873170 ..(H)

B. D-TYPE BUILDING (G+7)

AREA STATEMENT

Ground Floor	3335.60 sft	or	310.00 sqm
1st Floor	6245.10 sft	or	580.40 sqm
2nd Floor	6245.10 sft	or	580.40 sqm
3rd Floor	6245.10 sft	or	580.40 sqm
4th Floor	6245.10 sft	or	580.40 sqm
5th Floor	6245.10 sft	or	580.40 sqm
6th Floor	6245.10 sft	or	580.40 sqm
7th Floor	6245.10 sft	or	580.40 sqm
Built up area	47051.33 sft	or	4372.80 sqm
Stilt Area	3712.20 sft	or	345.00 sqm
Total Built up Area	50763.53 sft	or	4717.80 sqm

SL No.

DESCRIPTION

QUANTITY UNIT

RATE

AMOUNT

BUILDING COST (Specification as per Anx-I)

- 1 1.1 RCC Framed Structure (upto Six Storeys)
1.1.2 Floor height 3.00 mt
1.3.1 Set of Six additional storey (i.e from 7th to 12th storey)
1.3.2 Every 0.3 mtr. or part thereof, additional height of floor above normal floor height of 3.60 mtr. (on areas having less height)
(3.15-3.00)/0.30*421=210.50

4372.80 Sqm @ RS 210.50 /Sqm 920474

- 1.3.7 Pile foundation upto a depth of 15 metre (on ground floor area only)

Total Rs. 103882106 ..(a)

C.

ANNEXE BUILDING (G+3)**AREA STATEMENT**

Ground Floor	3176.89 sft	or	295.25 sqm
1st Floor	3019.79 sft	or	280.65 sqm
2nd Floor	3019.79 sft	or	280.65 sqm
3rd Floor	2829.88 sft	or	263.00 sqm
Total Built up Area	12046.36 sft	or	1119.55 sqm

Sl.
No.**DESCRIPTION****QUANTITY UNIT****RATE****AMOUNT****BUILDING COST (Specification as per Anx-I)**

1	1.1	RCC Framed Structure (upto Six Storeys)							
	1.1.2	Floor height 3.00 mt	1,119.55	sqm	@ RS	23530	/sqm	26343012	
	1.3.2	Every 0.3 mtr. or part thereof, additional height of floor above normal floor height of 3.60 mtr. (on areas having less height)							
		Proposed floor ht. = 3.30 m							
		$(3.30-3.00)/0.30 \times 421 = 421.00$							
			1119.55	Sqm	@ RS	421.00	/Sqm	471331	
								Total Rs.	26814343 ..(a)
	1.3.7	Pile foundation upto a depth of 15 metre (on ground floor area only)							
			295.25	Sqm	@ RS	19460	/Sqm	5745585	
								Total Rs.	32559908 ..(A)
	1.5	Fire Fighting							
	1.5.2	With wet riser system							
	1.6	Fire Alarm System	1119.55	Sqm	@ RS	890	/Sqm	996400	
	1.6.2	Automatic Fire alarm system							
			1119.55	Sqm	@ RS	600	/Sqm	671730	
								Total Rs.	1668130 ..(B)
2	2.1	Internal water supply and sanitary Installations @ 9 % of building basic cost(a)		9%					
	2.2	External service connection						2413291	
	2.2.1	Electrical External Service Connection @ 3.75 % of building basic cost(a)		3.75%				1005538	
	2.2.2	Civil External Service Connection @ 1.25 % of building basic cost		1.25%				335179	
	2.3	Internal electric Installations @ 12.5% of building basic cost(a)		12.5%				3351793	
								Total Rs.	7105801 ..(C)
								Total (A+B+C) Rs.	41333839 ..(D)
								(BUILDING+Services) PAR	3,431 /Sft
3	2.4.1	Power wiring and Plugs @ 4.0% of building basic cost(a)		4.0%				1072574	
	2.4.2	Lightning conductors @ 0.25% of building basic cost(a)		0.25%				67036	
	2.4.3	telephone conduits @ 0.25% of building basic cost(a)		0.25%				67036	
								Total Rs.	1206645 ..(E)
4	4.0	RCC WATER TANK							
	4.1	Overhead tank without independent staging	8000	ltr.	@ Rs	23	/ltr.	184000	
	4.5	Underground sump	30000	ltr.	@ Rs	23	/ltr.	690000	
								Total Rs.	874000 ..(F)
5	5	DEVELOPMENT OF SITE							
	5.1	Levelling							
	5.3	External Sewerage							
	5.4	Filtred water Supply							
	5.4.1	Distribution lines up to 100mm dia							
	5.4.2	Peripheral grid 150mm to 300 mm dia pipes							
	5.4.3	Unfiltred Water supply distribution lines.							
	5.5	Storm water drain.							
	5.6	Rain water Harvesting (RWH)							
	5.7	Trenches for services.							

1.5	Fire Fighting	310.00	Sqm	@ RS	19460	/Sqm	6032600	..(A)
1.5.2	With wet riser system						Total Rs. 109914706	
1.6	Fire Alarm System	4717.80	Sqm	@ RS	890	/Sqm	4198842	
1.6.2	Automatic Fire alarm system							
1.3.5	Making stronger foundations to take load of one additional floor (on ground floor area only)	4717.80	Sqm	@ RS	600	/Sqm	2830680	
1.8	Stilt Portion	310.00	Sqm	@ RS	1820	/Sqm	564200	
1.8.1	stilt portion of multi-storey buildings upto floor height of 3.60 metre (on stilt area only)							
2	2.1 Internal water supply and sanitary Installations @ 9 % of building basic cost(a)	345.00	Sqm	@ RS	9560	/Sqm	3298200	..(B)
	2.2 External service connection	9%					9349390	
	2.2.1 Electrical External Service Connection @ 3.75 % of building basic cost(a)	3.75%					3895579	
	2.2.2 Civil External Service Connection @ 1.25 % of building basic cost	1.25%					1298526	
	2.3 Internal electric Installations @12.5% of building basic cost(a)	12.5%					12985263	
	2.4.1 Power wiring and Plugs @ 4.0% of building basic cost(a)	4.0%					4155284	
							Total Rs. 31684042	..(C)
							Total (A+B+C) Rs. 152490670	..(D)
							(BUILDING+Services) PAR 3,004	/Sft
3	3.0 LIFTS with power operated centre opening doors and AC variable voltage & variable frequency controls.	2	No.	@ RS	2399100	each	4798200	..(E)
	3.1 Passenger Lift.							
	3.1.2 Passenger Lift. (13 prsn)							
4	4.0 RCC WATER TANK							
	4.1 Overhead tank without independent staging	15000	ltr.	@ Rs	23	/ltr.	345000	
	4.5 Underground sump	60000	ltr.	@ Rs	23	/ltr.	1380000	
							Total Rs. 1725000	..(F)
5	5 DEVELOPMENT OF SITE							
	5.1 Levelling							
	5.3 External Sewerage							
	5.4 Filtred water Supply							
	5.4.1 Distribution lines up to 100mm dia							
	5.4.2 Peripheral grid 150mm to 300 mm dia pipes							
	5.4.3 Unfiltred Water supply distribution lines.							
	5.5 Storm water drain.							
	5.6 Rain water Harvesting (RWH)							
	5.7 Trenches for services.							
	5.9 Horticulture work @ 7.5% of basic building cost (a)	103882106.00		7.50%			7791158	..(G)
							Total Rs. 7791158	
6	6.8 Solar Photo Voltaic Power Generation System	20.00	kWp	@ RS	58480	/kWp	1169600	
	6.10.2 CCTV System	4717.80	Sqm	@ RS	210	/Sqm	990738	
	6.16.1 Lan System	4372.80	Sqm	@ RS	560	/Sqm	2448768	
							Total Rs. 4609106	..(H)
							Total (D+E+F+G+H) Rs. 171414134	

5.9 Horticulture work
@ 7.5% of basic building cost (a)
26814343.00

6 6.8 Solar Photo Voltaic Power Generation System 7.50%

6.10.2 CCTV System

6.16.1 Lan System

6.18 Conference hall: supplying, installation, testing and commissioning of audio visual/conference system
(Rate applicable on carpet area of Hall only)
Meeting Room

8.00	kWp	@ RS	58480	/kWp	467840	2011076	2011076	..(G)
1119.55	Sqm	@ RS	210	/Sqm	235106			
1119.55	Sqm	@ RS	560	/Sqm	626948			
41.08	Sqm	@ RS	11890	/Sqm	488441			
Total (D+E+F+G+H) Rs.					1818335	47243895		..(H)

D. GUARD ROOM(G)-2 Nos.

AREA STATEMENT

Ground Floor

Total Built up Area

209.82 sft

209.82 sft

or

19.50 sqm

or

19.50 sqm

DESCRIPTION

QUANTITY UNIT

RATE

AMOUNT

1	1.1	RCC Framed Structure (upto Six Storeys)	19.50	Sqm	@ Rs	23530	/sqm	458835		
	1.1.2	Floor height 3.00 mt						458835		..(a)
	1.3.4	Every 0.30 m or part thereof, deeper foundations over normal depth of 1.20 m (on ground floor area only)	19.50	Sqm	@ Rs	230	/Sqm	4485		
2	2.1	Internal water supply and sanitary Installations @ 9 % of building basic cost(a)	9%					463320		..(A)
	2.3	Internal electric Installations @ 12.5% of building basic cost(a)	12.5%					41295		
	2.4.1	Power wiring and Plugs @ 4.0% of building basic cost(a)	4.0%					57354		
								18353		
								117002		..(B)
								580322		..(C)
								2,766		/Sft
4	4.0	RCC WATER TANK	1000	ltr.	@ Rs	23	/ltr.	23000		
	4.1	Overhead tank without independent staging						23000		..(D)

5 DEVELOPMENT OF SITE

- 5.1 Levelling
- 5.3 External Sewerage
- 5.4 Filtred water Supply
- 5.4.1 Distribution lines up to 100mm dia
- 5.4.2 Peripheral grid 150mm to 300 mm dia pipes
- 5.4.3 Unfiltred Water supply distribution lines.
- 5.5 Storm water drain.
- 5.6 Rain water Harvesting (RWH)
- 5.7 Trenches for services.
- 5.9 Horticulture work
@ 4.5% of basic building cost (a)
458835.00

7.50%

6 6.8 Solar Photo Voltaic Power Generation System

6.10.2 CCTV System

1.00	kWp	@ RS	58480	/kWp	58480	34413	34413	..(E)
19.50	Sqm	@ RS	210	/Sqm	4095			
Total (C+D+E+F) Rs.					62575	700310		..(F)
Hence, Cost For 2 Guard Room					700310	1400621		

Cost For 1 Guard Room
Hence, Cost For 2 Guard Room


700310 x2 =


E. Internal Road & Boundary Wall


5.2	Internal Road & path.						
5.2.3	Cement Concrete Pavement with Vacuum deaired concrete.	1,900.00 (Approx)	sqm	@ Rs	2320		
5.8	Boundary wall with 1500mm high wall from & 600 mm high MS grill including 2100mm high steel gates at every 100 mtr.						
5.8.1	With brick work structure and RCC band at ground level and coping.	430.00 (Approx)	sqm	@ Rs	10870		
6.29	Motorized steel gates upto 6.00 metre width	2.00	gate	@ Rs	500000		
						Total	

F. SPECIALISED E&M WORKS

6.2	Sub-Station Equipment						
6.2.1	Supplying, Installation, testing and commissioning of 33 kV/0.433 kV or 11 kV/0.433 kV substation equipment comprising HT panel, transformer, power factor.....	800.00	kVA	@ Rs	9000	/kVA	7200000
6.3	Diesel Generating Sets						
6.3.1	Supplying, installation, testing and commissioning of silent type DG sets, set, AMF panel, bus ducting/cables.....	300	kVA	@ Rs	11560	/kVA	3468000
						Total	10668000


J.E.
Adv. Planning Div.-2
BCD, Patna


A.E.
Adv. Planning Div.-2
BCD, Patna


E.E.
Adv. Planning Div.-2
BCD, Patna