

कार्यपालक अभियंता का कार्यालय
पुनपुन बाढ़ सुरक्षा प्रमंडल, अनिसाबाद, पटना ।
जल संसाधन विभाग, पटना ।

अल्पकालीन कोटेशन आमंत्रण सूचना सं0- 36, वर्ष 2025-26

सिंचाई भवन, हार्डिंग रोड, पटना में स्थित जल संसाधन विभाग के विभिन्न कार्यालयों का मरम्मत एवं विभिन्न सामग्रीयों की आपूर्ति एवं अधिष्ठापन कार्य हेतु संवेदक/आपूर्तिकर्ता से मुहरबंद लिफाफा में कोटेशन आमंत्रित की जाती है।

यह कोटेशन दिनांक- 10.02.2026 को अपराह्न 3:00 बजे तक अधोहस्ताक्षरी के कार्यालय में प्राप्त किया जाएगा और उसी दिन 3:30 बजे अपराह्न में कोटेशन दाताओं या उनके द्वारा प्राधिकृत प्रतिनिधियों के समक्ष खोला जाएगा।

कार्य दिवरणी :- ग्रुप- 01- Name of work- Beautification of Corridor near main gate, Partition wall for bathroom at first floor & Other miscellaneous work, Sinchai Bhawan, Patna. **(Non Schedule Item)** का कार्य।

Si. No.	Description of work/Supply	Unit	Qty	Rate Quoted (Rs. Per Unit) in figure & words also
1	2	3	4	5
1	Providing and fixing Partition wall made of Designer MDF board fixed on the vertical pillar & Horizontal frame made of 2"x1.5" aluminium channel with 12 mm thick plywood surface finished with 1 mm thick sunmica & MDF designer board fixed with toughened glass with 1 mm thick film & MDF designer board paint with deco paint complete job - As per design.	Sqft	87.59	
2	Providing and fixing of Decorative door with frame of 32 mm ply board surface finished with 1 mm lamination both side with all fitting's complete jobs.	Sqft	55.22	
3	Demolishing of Existing damaged false ceiling etc and disposal of scrap material at suitable place.	Item	1.00	
4	Providing and fixing Gypsum false ceiling system using 12 mm thick gypsum board fixed on aluminium channel of size 2"x1" in ceiling as per design with all necessary fittings, steel screw, rowel plug etc. as per specification and direction of E/I complete job.	Sqft	281.51	
5	Making a electric Pannel openable box using 12 mm thick ISI marked water proof plywood including handle, magnet & all fitting materials and surface finished with 1mm sunmica etc all complete jobs.	Sqft	10.82	
6	Providing and fixing Designer false ceiling using 18 mm thick WPC board hanging in ceiling by aluminium channel of size 2.5" x 1.5" and surface finished with sunmica and making required design with all necessary fittings, steel screw, rowel plug etc. as per specification and direction of E/I complete job.	Sqft	144.00	
7	Decorative Wall panelling to be made with plywood on single sides above Aluminium Frame 2"x1" with best quality ISI marked waterproof century ply club prime of 12 mm thick ply wood finished with decorative Lamination of 1mm thick sunmica of one side with necessary adhesive & screws all complete job.	Sqft	95.78	

R

8	Decorative Wall panelling with 1.0 mm thick Lamination of approved design over base of 12 mm thick ISI marked water proof Plywood over aluminium channel of size 2"x1" ' fixed on the wall and surface finished with Louvers having rise & tread by using necessary adhesive and fixture etc. as per the design, all exposed edges covered with polished, complete job	Sqft	92.08	
9	Making frame of size 2.5" height/Width by using 12 mm thick plywood surface finished with lamination of 1 mm thick sunmica and supplying & placing of Designer stone and frame fixed on the surface etc all complete jobs.	ft	23.00	
10	Providing and Fixing Spot Pannel light 4" dia fixed on the ceiling as per design.	Each	10.00	
11	Providing & fixing LED Profile light fixed in the ceiling including all fittings complete job.	Rft	44.00	
12	Providing and fixing of square light in ceiling 2'0"x2'0", 36-Watt complete job	Each	4.00	
13	Supplying and fixing privacy window frosted glass film no glue Anti-UV window sticker Adhesive for privacy etc all complete jobs	Sqft	15.00	
14	Supplying and fitting Copper Wire 1.5 MM	m	90.00	
15	Supply and fixing of 2 m length internet cable etc all complete jobs.	Each	1.00	
16	Supplying of high-pressure car washing machine 1800 watts and pressure 120 bar for cleaning car etc including pipes all complete jobs.	Each	1.00	
17	Repair of wardrobe including self-channel etc complete jobs	Item	1.00	
18	Providing and fixing of heavy-duty Automatic door closer etc all complete jobs	No	2.00	
19	Providing and fixing of steel pipe for curtain all complete jobs	Ft	10.00	
20	Supplying of Small Ceramic plates for snacks at the time of meeting for Conference Hall.	Each	24.00	
21	Providing and fixing wardrobe having inner shelves as per design for storing files made of 12mm & 19 mm thick ISI marked water proof Plywood finished with decorative Lamination of 1mm thick sunmica with necessary adhesive & screws all complete job.	Sqft	35.00	
22	Supplying of Flower plant etc all complete jobs.	Each	1200.00	
23	Supplying of Plastic flower pots 10 inch dia etc all complete jobs.	Each	100.00	
24	Providing, placing and fixing in position of 3-Seater customized sofa having size 2100x700 mm made up of Suede/Leatherite upholstery on frame of wood and plywood, as per direction of Engineer-in-Charge.	Each	1.00	
25	Providing, placing and fixing in position of Single seater Customized sofa having size 900x700 mm made up of Suede/Leatherite upholstery on frame of wood and plywood, as per direction of Engineer-in-Charge.	Each	2.00	
26	Supplying of premium sofa cushion 16x16 inch including cover etc all complete jobs.	Each	6.00	
27	Supply, Fitting and fixing of wall fan Havells / Polar or equivalent.	Each	2.00	
28	Supplying of Customised wooden chair made of Sangwan wood as per design all complete jobs.	Each	2.00	
29	Supplying of Customized chair orthopaedic foam cushion etc all complete jobs	Each	4.00	


30	Making a wooden tool of size 1'0" x 1'0" with all fittings complete jobs	Each	1.00	
31	Supplying and fixing wardrobe rack of 12 mm plyboard of size 2'0" x 0'9" and surface finished with 1 mm sunmica with all required fittings complete jobs	Each	2.00	

युप- 02 Supply, installation of Telephone and maintenance of EPABX System at WRD, Sinchai Bhawan, Patna. का कार्य।

Si. No.	Description of work/Supply	Unit	Qty	Rate Quoted (Rs. Per Unit) in figure & words also
1	2	3	4	5
1	Maintenance of EPABX System upto 31.03.2026	No	1	
2	Phone Set with Clip	No	10	
3	Cabling 4 pair telephone cable through PVC conduit.	m	305	
4	Cabling with telephone cable 2 pair with casing laying and fitting.	m	580	
5	Digital Phone set with 12 Programable key.	No	2	
6	Trunk card 04 port.	No	1	
7	Digital expansion card 8 port	No	1	

उपरोक्त कोटेशन से संबंधित शर्त एवं विशेष जानकारी हेतु अधोहस्ताक्षरी कार्यालय में (कार्यालय अवधि में) एवं मोबाईल संख्या- 7463889527 पर सम्पर्क किया जा सकता है।

इसे विस्तृत रूप में बेवसाईट www.prdbihar.gov.in पर देखा जा सकता है।


 कार्यपालक अभियंता
 पुनपुन बाढ़ सुरक्षा प्रमंडल
 अनिसाबाद, पटना।

कार्यपालक अभियंता का कार्यालय
पुनपुन बाढ़ सुरक्षा प्रमंडल, अनिसाबाद, पटना ।
जल संसाधन विभाग, पटना ।

अल्पकालीन कोटेशन आमंत्रण सूचना सं०- 36, वर्ष 2025-26

सिंचाई भवन, हार्डिंग रोड, पटना में स्थित जल संसाधन विभाग के विभिन्न कार्यालयों का मरम्मत एवं विभिन्न सामग्रीयों की आपूर्ति एवं अधिष्ठापन कार्य हेतु निबंधित संवेदक/आपूर्तिकर्ता से मुहरबंद लिफाफा में कोटेशन आमंत्रित की जाती है।

यह कोटेशन दिनांक- 10.02.2026 को अपराह्न 3:00 बजे तक अधोहस्ताक्षरी के कार्यालय में प्राप्त किया जाएगा और उसी दिन 3:30 बजे अपराह्न में कोटेशन दाताओं या उनके द्वारा प्राधिकृत प्रतिनिधियों के समक्ष खोला जाएगा।

कार्य विवरणी :- ग्रुप- 01-Name of work- Beautification of Corridor near main gate, Partition wall for bathroom at first floor & Other miscellaneous work, Sinchai Bhawan, Patna. **(Non Schedule Item)** का कार्य।

Si. No.	Description of work/Supply	Unit	Qty	Rate Quoted (Rs. Per Unit) in figure & words also
1	2	3	4	5
1	Providing and fixing Partition wall made of Designer MDF board fixed on the vertical pillar & Horizontal frame made of 2"x1.5" aluminium channel with 12 mm thick plywood surface finished with 1 mm thick sunmica & MDF designer board fixed with toughened glass with 1 mm thick film & MDF designer board paint with deco paint complete job - As per design.	Sqft	87.59	
2	Providing and fixing of Decorative door with frame of 32 mm ply board surface finished with 1 mm lamination both side with all fitting's complete jobs.	Sqft	55.22	
3	Demolishing of Existing damaged false ceiling etc and disposal of scrap material at suitable place.	Item	1.00	
4	Providing and fixing Gypsum false ceiling system using 12 mm thick gypsum board fixed on aluminium channel of size 2"x1" in ceiling as per design with all necessary fittings, steel screw, rowel plug etc. as per specification and direction of E/I complete job.	Sqft	281.51	
5	Making a electric Pannel openable box using 12 mm thick ISI marked water proof plywood including handle, magnet & all fitting materials and surface finished with 1mm sunmica etc all complete jobs.	Sqft	10.82	
6	Providing and fixing Designer false ceiling using 18 mm thick WPC board hanging in ceiling by aluminium channel of size 2.5" x 1.5" and surface finished with sunmica and making required design with all necessary fittings, steel screw, rowel plug etc. as per specification and direction of E/I complete job.	Sqft	144.00	
7	Decorative Wall panelling to be made with plywood on single sides above Aluminium Frame 2"x1" with best quality ISI marked waterproof century ply club prime of 12 mm thick ply wood finished with decorative Lamination of 1mm thick sunmica of one	Sqft	95.78	

✍

	side with necessary adhesive & screws all complete job.			
8	Decorative Wall panelling with 1.0 mm thick Lamination of approved design over base of 12 mm thick ISI marked water proof Plywood over aluminium channel of size 2"x1" fixed on the wall and surface finished with Louvers having rise & tread by using necessary adhesive and fixture etc. as per the design, all exposed edges covered with polished , complete job	Sqft	92.08	
9	Making frame of size 2.5" height/Width by using 12 mm thick plywood surface finished with lamination of 1 mm thick sunmica and supplying & placing of Designer stone and frame fixed on the surface etc all complete jobs.	ft	23.00	
10	Providing and Fixing Spot Pannel light 4" dia fixed on the ceiling as per design.	Each	10.00	
11	Providing & fixing LED Profile light fixed in the ceiling including all fittings complete job.	Rft	44.00	
12	Providing and fixing of square light in ceiling 2'0"x2'0", 36-Watt complete job	Each	4.00	
13	Supplying and fixing privacy window frosted glass film no glue Anti-UV window sticker Adhesive for privacy etc all complete jobs	Sqft	15.00	
14	Supplying and fitting Copper Wire 1.5 MM	m	90.00	
15	Supply and fixing of 2 m length internet cable etc all complete jobs.	Each	1.00	
16	Supplying of high-pressure car washing machine 1800 watts and pressure 120 bar for cleaning car etc including pipes all complete jobs.	Each	1.00	
17	Repair of wardrobe including self-channel etc compleet jobs	Item	1.00	
18	Providing and fixing of heavy-duty Automatic door closer etc all complete jobs	No	2.00	
19	Providing and fixing of steel pipe for curtain all complete jobs	Ft	10.00	
20	Supplying of Small Ceramic plates for snacks at the time of meeting for Conference Hall.	Each	24.00	
21	Providing and fixing wardrobe having inner shelves as per design for storing files made of 12mm & 19 mm thick ISI marked water proof Plywood finished with decorative Lamination of 1mm thick sunmica with necessary adhesive & screws all complete job.	Sqft	35.00	
22	Supplying of Flower plant etc all complete jobs.	Each	1200.00	
23	Supplying of Plastic flower pots 10 inch dia etc all complete jobs.	Each	100.00	
24	Providing, placing and fixing in position of 3-Seater customized sofa having size 2100x700 mm made up of Suede/Leatherite upholstery on frame of wood and plywood, as per direction of Engineer-in-Charge.	Each	1.00	
25	Providing, placing and fixing in position of Single seater Customized sofa having size 900x700 mm made up of Suede/Leatherite upholstery on frame of wood and plywood, as per direction of Engineer-in-Charge.	Each	2.00	
26	Supplying of premium sofa cushion 16x16 inch including cover etc all complete jobs.	Each	6.00	
27	Supply, Fitting and fixing of wall fan Havells / Polar or equivalent.	Each	2.00	
28	Supplying of Customised wooden chair made of Sangwan wood as per design all complete jobs.	Each	2.00	

29	Supplying of Customized chair orthopaedic foam cushion etc all complete jobs	Each	4.00	
30	Making a wooden tool of size 1'0" x 1'0" with all fittings complete jobs	Each	1.00	
31	Supplying and fixing wardrobe rack of 12 mm plyboard of size 2'0" x 0'9" and surface finished with 1 mm sunmica with all required fittings complete jobs	Each	2.00	

ग्रुप- 02 Supply, installation of Telephone and maintenance of EPABX System at WRD, Sinchai Bhawan, Patna. का कार्य।

Si. No.	Description of work/Supply	Unit	Qty	Rate Quoted (Rs. Per Unit) in figure & words also
1	2	3	4	5
1	Maintenance of EPABX System upto 31.03.2026	No	1	
2	Phone Set with Clip	No	10	
3	Cabling 4 pair telephone cable through PVC conduit.	m	305	
4	Cabling with telephone cable 2 pair with casing laying and fitting.	m	580	
5	Digital Phone set with 12 Programable key.	No	2	
6	Trunk card 04 port.	No	1	
7	Digital expansion card 8 port	No	1	

नियम एवं शर्त :-

- कोटेशन दाताओं को अपना दर अंक एवं अक्षरों में प्रतियूनिट उद्धृत करना होगा।
- कोटेशनदाता से कोटेशन अलग-अलग ग्रुप के अनुसार मुहरबंद एवं परिभाषित लिफाफा में प्राप्त किया जाएगा।
- कोटेशन दाता को कोटेशन के साथ अपना जी० एस० टी० निबंधन एवं पैन कार्ड का स्व० अभिप्रमाणित छायाप्रति संलग्न करना अनिवार्य होगा।
- भुगतान के समय कोटेशनदाता/आपूर्तिकर्ता द्वारा जी०एस०टी० अधिनियम के अधीन अद्यतन विवरणियाँ दाखिल करने संबंधी प्रमाण पत्र संलग्न करना अनिवार्य होगा।
- कोटेशनदाता द्वारा निविदा कागजातों के साथ संलग्न किये जाने वाले कागजातों की सत्यता के संबंध में एक घोषणा का शपथ पत्र के रूप में दिया जाना आवश्यक होगा। घोषणा पत्र का प्रारूप निम्नवत् होगा:-

I the under signed do here by certify that all the statements made in the required attachments are true and correct and if found fake/forged, the under signed will be liable for infliction upon the FIR and lawful punishment as well as black listing.

- कोटेशनदाता को अग्रधन की राशि के रूप में कोटेशन के सिर्फ ग्रुप- 1 में रू०- 10,000.00 (दस हजार) कोटेशनदाता को मान्य प्रतिभूति, यथा छः राष्ट्रीय बचत पत्र अथवा चालू निर्गम डाकघर सावधि जमा 1, 2 एवं 3 वर्षीय पास बुक अथवा बिहार वित्त नियमावली के अनुसार मान्य प्रतिभूति जिसे "कार्यपालक अभियंता, पुनपुन बाढ़ सुरक्षा प्रमंडल अनिसाबाद/Executive Engineer, Punpun Flood Protection Division Anisabad, Patna" के नाम से प्रतिज्ञिप्त जमा करना होगा अग्रधन की राशि जमा नहीं होने की स्थिति में कोटेशन मान्य नहीं होगी शेष अग्रधन की राशि कार्य के एकरारनामा के समय जमा करना होगा।



- (7) ग्रुप- 01 के लिए संवेदक/एजेंसी को एकरारनामा के समय आचरण प्रमाण पत्र संलग्न करना होगा।
- (8) किसी प्रकार का अतिरिक्त दुलाई देय नहीं होगा।
- (9) सशर्त कोटेशन स्वीकार नहीं किया जाएगा।
- (10) अधोहस्ताक्षरी को कोटेशन रद्द करने का अधिकार सुरक्षित होगा।
- (11) कोटेशन में उल्लेखित सामग्री की मात्रा घट एवं बढ़ सकती है तदुनुरूप आपूर्ति आदेश निर्गत किया जायेगा।
- (12) न्यूनतम दरदाता के द्वारा उल्लेखित सामग्री हेतु उद्धृत स्वीकृत दर वित्तीय वर्ष 2025-26 तक के लिए मान्य होगी।
- (13) सफल कोटेशनदाता के विपत्र से सभी नियमानुकूल कटौतियों की जायेगी।
- (14) कार्य अवधि ग्रुप- 1 के लिए 20 दिन एवं ग्रुप- 2 के लिए 10 दिन होगी।

उपरोक्त कोटेशन से संबंधित शर्त एवं विशेष जानकारी हेतु अधोहस्ताक्षरी कार्यालय में (कार्यालय अवधि में) एवं दूरभाष संख्या- 7463889527 पर सम्पर्क किया जा सकता है।

इसे विस्तृत रूप में वेबसाईट www.prdbihar.gov.in पर देखा जा सकता है।

ह०/-

कार्यपालक अभियंता
पुनपुन बाढ़ सुरक्षा प्रमंडल
अनिसाबाद, पटना।


पत्रांक.....195...

पटना,

दिनांक.....29/01/2026 / 2026

प्रतिलिपि:- सूचना एवं जनसम्पर्क पदाधिकारी, जल संसाधन विभाग, सिंचाई भवन, पटना को सूचनार्थ एवं दैनिक समाचार पत्र एवं वेबसाईट के माध्यम से प्रचार-प्रसार हेतु समर्पित।

अनु० :- यथावत्।



कार्यपालक अभियंता
पुनपुन बाढ़ सुरक्षा प्रमंडल
अनिसाबाद, पटना।