Office of the Executive Engineer (Mech.),
Irrigation Mechanical Division, Birpur

E-mail ID:- imdbirpur@gmail.com

Letter No. --2066-- Birpur Date :--22-10-26--

Emergent NIQ No.- 15/2026-27

1. Designation of Quotation Inviter :- **Executive Engineer (Mech.), Irrigation Mechanical Division, Birpur**
2. Date of Invitation :- **22.10.2026**
3. Date of Receiving Quotation :- **30.10.2026 up to 3.00 PM only.**
4. Date of Opening Quotation :- **30.10.2026 At 3.30 PM .**

SL. No.	Item of Work	Unit	Qty.	Rate		Amount
				Rate with Transportation	GST	
1.	Provision for fabrication, erection, supply, installation, testing and commissioning of floor mounting, single front, fixed type CRCA sheet fabricated Main control panel for electrically operated hoisting system of 2 nos. of under sluice and 11 nos. spillway and lighting arrangement of cross regulator etc. all copper fire resistant cable (Simens, Havells or equivalent)with incomer 630 A MCCB TPN AND 250A Changeover switch OUT going reverse forward stop starter with limit switch, Emergency stop, selector switch, Voltmeter, ammeter, local control of all C/R gate for 3 HP Motor and 250 A MCCB -1 no, 63 A 4 POLE MCB-6 No, 40 A DP MCB- 20 Nos(simens, schneider or equivalent), IP 65 protection class with RYB Indicating lamp From distribution box to whole cross regulator with connected cable tray, electrification system, Earthing, siren, lightening at cross regulator area, main control panel, junction Box, Control Room panel lightening and control panel consisting of bus bar, Changeover Switch, limit switch, Control switch, MCB trip indicators lamps. LED flood light with 3 M stand with all required accessoriesWith latest BIS code with amendments and as per requirement of siteetc. Including cost of all materials, labour, machinery, cutting, aligning, anchoring, welding, Finishing, applying 2 coats of Zinc chromate primer and 3 coats of synthetic aluminium paint as per direction of E/I.	Each	1 No.			
2.	Provision for fabrication, supply, transportation, earthing, installation, testing, commissioning of electrically operated rope drum system hoist of 10 MT capacity consisting of structural base frame, Gear chamber, connecting gear box, Plummer block with bearing (SKFor equivalents), rope drum, steel wire rope Dia. 19 mm, Manual operation assembly system, dial indicator, connecting line shaft, Coupling, Standard make Reduction gear box unit (Premium, Radicon, Greaves or equivalent) With latest BIS code with amendments and as per requirement of site etc. all complete job Including cost of all materials, labour, machinery, cutting, aligning, anchoring, welding, Finishing, applying 2 coats of Zinc chromate primer and 2 coats of synthetic aluminium paint as per direction of E/I.	Each	13 Nos.			

3.	Provision for Supply, transportation, erection, installation, testing, commissioning of 415V 3 Phase 3 HP squirrel case induction motor(Premium, Havells, Crompton or equivalent) electromagnetic brake system with drum, gate position indicator,CRCA sheet fabricated IP65 Local control panelconsisting of bus bar including Local control reverse forward starter with reverse forward stop starter with limit switch, Emergency stop, selector switch, Voltmeter, ammeter, local control of all C/R gate for 3 HP Motor and emergency push button, manual operation assembly system with fixed MS frame cover, latching pad as per requirement of site with all accessories for easy operation of cross regulator under sluice gates and spillway gates (As per latest BIS code with amendments) etc. all complete job Including cost of all materials, labour, machinery, cutting, aligning, anchoring, welding, Finishing, applying 2 coats of Zinc chromate primer and 2 coats of synthetic aluminium paint as per direction of E/I.	Each	13 Nos.			

22/10/26

Executive Engineer (Mech.),
Irrigation Mechanical Division, Birpur
Mob. No.-8210141033

Terms & Conditions

(1) कोटेशनदाता अंकित Format में अथवा अपने Letter Pad पर दर समर्पित करेगें।

(2) कोटेशनदाता अंकित सामाग्रियों का दर/राशि अंक एवं अक्षरों में अलग–अलग (Rate with Transportation & GST) उद्धृत कर दिनांक **30.10.2026** के 3.00 बजे अपराह्न तक हाथोंहाथ/निबंधित डाक/E-mail ID:-i***mdbirpur@gmail.com*** के माध्यम से समर्पित कर सकते है, जो दिनांक **30.10.2026** को 3.30 बजे अपराह्न में Download अथवा खोला जायेगा।

(3) कोटेशनदाताओं को कोटेशन के साथ GST निबंधन एवं PAN Card का स्व–अभिप्रमाणित छायाप्रति संलग्न करना अनिवार्य होगा तथा कोटेशन पर GST No. एवं PAN No. अंकित किया जाना अनिवार्य होगा।

(4) सशर्त्त कोटेशन स्वीकार नहीं किया जायेगा।

(5) यह कोटेशन मात्र दर प्राप्ति हेतु आमंत्रित किया गया है, अतएव कोटेशनदाता द्वारा किसी भी प्रकार का कार्यावंटन का दावा मान्य नहीं होगा।

(6) अधिक जानकारी हेतु कार्यपालक अभियंता (यॉत्रिक), सिंचाई यॉत्रिक प्रमंडल, वीरपुर के मोबाईल नं0–8210141033 पर सम्पर्क किया जा सकता है।

(7) कोटेशनदाता E-mail ID:- imdbirpur@gmail.com पर Soft Copy प्राप्ति हेतु अनुरोध कर सकते है।

(8) सूचना विभागीय बेवसाईट wrd.bihar.gov.in पर भी देखा जा सकता है।

22/10/26

Executive Engineer (Mech.),
Irrigation Mechanical Division, Birpur
Mob. No.-8210141033